

RECEIVED

MAR 28 2002

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 119-21065-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Raydon Exploration, Inc. KCC LICENSE # 30604

ADDRESS 9400 N. Broadway, Ste. 400 CITY Oklahoma City  
(owner/company name) (operator's)

STATE OK ZIP CODE 73114 CONTACT PHONE # (620) 624-0156

LEASE Calhoun WELL# 1-13 SEC. 13 T. 33S R. 29 (East/West)

- NW - SE SPOT LOCATION/0000 COUNTY Meade

1980 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE 20" SET AT 54' CEMENTED WITH 6 sacks groutsacks

SURFACE CASING SIZE 8-5/8" SET AT 1613' CEMENTED WITH 775 lead, 150sacks

PRODUCTION CASING SIZE 4-1/2" SET AT 3155' CEMENTED WITH 225 lead, 125sacks  
tail

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5666-5676', CIBP @5600' w/2 sacks, 3009-3013'  
tail

ELEVATION 2461' GL T.D. 6240' PBD 3154' ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP at 2990' with 2 sacks cement, cut

off at 2000', lay down casing, spot 50 sack plug at 1650', 40 sack plug at 500', 10 sack plug at 40-4', cut off 4' below ground level and  
(if additional space is needed attach separate page)weld on ID plate.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Attached

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Keith Hill PHONE# 620-624-0156

ADDRESS Crown Consulting, Inc. City/State Liberal, KS 67905-1816  
PO Box 1816

PLUGGING CONTRACTOR Sargent & Horton KCC LICENSE # 31151

ADDRESS Rt 1 box 49BA, Tyrone, OK 73951 PHONE # (580) 854-6515  
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 04-05-02

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-22-02 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)



## *Kansas Corporation Commission*

*Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Raydon Exploration, Inc.  
9400 N. Broadway #400  
Oklahoma City, OK 73114

April 01, 2002

Re: CALHOUN #1-13  
API 15-119-21065-00-00  
NWSE 13-33S-29W, 1980 FSL 1980 FEL  
MEADE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor