

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21964-00-00
Spot: CNE Sec/Twnshp/Rge: 1-34S-35W
3907 feet from S Section Line, 1267 feet from E Section Line
Lease/Unit Name: WHEELER Well Number: 1-2
County: STEVENS Total Vertical Depth: 2900 feet

Operator License No.: 4742
Op Name: TEXACO EXPL. AND PROD. INC.
Address: PO BOX 277
VELMA, OK 73491

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 641 WITH 375 SX CMT
Production: Size 4.5 feet: 2899 WITH 540 SX CMT ⁸
Liner: Size feet: 94.25

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/17/2001 3:30 PM
Plug Co. License No.: 31705 Plug Co. Name: H & K PLUGGING AND SALVAGE
Proposal Rcvd. from: JIM CONNER Company: H & K PLUGGING AND SALVAGE Phone: (806) 665-2550

Proposed Plugging Method: CIBP @ 2606'. 1ST PLUG AT 1600' WITH 30 SX CMT. 2ND PLUG AT 670' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/17/2001 6:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2859. PERFS AT 2656-2792'. 1ST PLUG SET CIBP @ 2590' & DUMPED 2 SX CMT ON TOP WITH DUMP BAILER. 2ND PLUG RAN 2 3/8" TUBING IN HOLE TO 1600'. LOADED HOLE WITH MUD AND PUMPED 30 SX CMT. HAD CIRCULATION TO SURFACE. 3RD PLUG PULLED TUBING UP TO 670' PUMPED 30 SX CMT. 4TH PLUG PULLED UP TO 40' AND PUMPED 10 SX CMT. 8 5/8" X 4 1/2" ANNULUS CMT AT SURFACE.

INVOICED
DATE 5-29-01
INV. NO. 2001061834
RECEIVED
KANSAS CORPORATION COMMISSION
MAY 23 2001
CONSERVATION DIVISION

Remarks: USED CLASS A CEMENT BY H & K PLUGGING. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Kevin D. Strube
(TECHNICIAN)

MAY 21 2001

Form CP-2/3

MP