

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19164-00-00
Spot: SENENW Sec/Twnshp/Rge: 3-25S-5E
4290 feet from S Section Line, 3239 feet from E Section Line
Lease Name: FRANK ROBISON Well #: 24
County: BUTLER Total Vertical Depth: 2447 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2195		
PROD	5.5	2415		0 SX
SURF	12	132		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2015 8:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY INC. Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/17/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2365', DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. TESTED CASING, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES 250'-251' (4 HOLES). SWEDGED INTO 5 1/2" CASING, CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 205 SXS 60/40 POZMIX 4% GEL 2% CC 1/2# POLY FLAKE TO SURFACE. CEMENT CIRCUALTED. CONSOLIDATED CEMENT TICKET #48543.

Perfs:

Top	Bot	Thru	Comments
2415	2447	OH	

Remarks:

Plugged through: TBG

5/13/15 CKM

District: 02

Signed DUANE KRUEGER

(TECHNICIAN)

KCC WIC: 1111

MAY 11 2015

RECEIVED

1/4