

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19165-00-00  
Spot: SWNWNWNE Sec/Twnshp/Rge: 3-25S-5E  
4658 feet from S Section Line, 2514 feet from E Section Line  
Lease Name: FRANK ROBISON Well #: 25  
County: BUTLER Total Vertical Depth: 2456 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	2455		
PROD	7	2455		0 SX
SURF	13	100		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2015 8:00 AM  
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC  
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY CO. Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/17/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2300', DUMP BAILED 4 SXS CEMENT ON TOP OF SAND. TESTED CASING, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES 250'-251' (4 HOLES). SWEDGED INTO 4 1/2" CASING, CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL 2% CC 1/2# POLY FLAKE TO SURFACE. CEMENT CIRCULATED TO SURFACE ON INSIDE OF 7". RIH W/ 1" TBG BETWEEN 7" & 13" @ 186', CONSOLIDATED OIL WELL ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. P&A COMPLETE. CONSOLIDATED CEMENT TICKET #48544.

Perfs:

Top	Bot	Thru	Comments
2455	2456	OH	

Remarks:

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

KCC WICHITA

MAY 11 2015

RECEIVED

JK

5/13/15 CKM