

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21485-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 2-26S-4E
1656 feet from S Section Line, 4936 feet from E Section Line
Lease Name: PAULSON Well #: 7B
County: BUTLER Total Vertical Depth: 2461 feet

Operator License No.: 5446
Op Name: GILES, BENJAMIN M.
Address: 346 S. LULU
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2460	270	180 SX
SURF	8.63	162		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2015 8:00 AM
Plug Co. License No.: 5446 Plug Co. Name: GILES, BENJAMIN M.
Proposal Rcvd. from: DUSTY GREEN Company: GILES, BENJAMIN M. Phone: (316) 655-7542

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2015 1:45 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) RAN IN WITH TUBING AND BRIDGED ON POSSIBLY EITHER CEMENT OR CIBP AT 2368'. 2) PUMPED 10 SKS OF 60/40/4% CEMENT AT 2358' THROUGH TUBING. 3) PULLED UP TO 2072' AND PUMPED 50 KS CEMENT W/ 75 LBS HULLS. 4) PULLED TUBING OUT OF HOLE AND RAN IN W/ WIRELINE. TAGGED CEMENT AT APPROX. 1521'. 5) CASING SHOT OFF AT 270' AND PULLED. 6) RUN IN WITH TUBING TO APPRO 250' AND PUMP 135 SKS CEMENT. CIRCULATED TO SURFACE. 5/5/2015 CHECKED TOP PLUG WAS AT SURFACE, WELL WILL BE BURIED APPROX. 5' BELOW SURFACE.

Perfs:

Top	Bot	Thru	Comments
2420	2424	CSG	
2396	2406	CSG	
1984	2068	CSG	

Remarks: CEMENTING COMPLETED BY GRESSEL OILFIELD SERVICE, LLC. HAYSVILLE, KS. TICKET #43060. PLUGGED DUE TO DENIED TA FOR HIGH FLUID LEVEL.

Plugged through: TBG

5/13/15 CKM

District: 02

Signed Jonathan Hill
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

MAY 08 2015

RECEIVED