

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22306-00-00**Spot:** NESENE**Sec/Twnshp/Rge:** 6-26S-5E1650 feet from N Section Line, 330 feet from E Section Line**Lease Name:** MARSH A**Well #:** 8**County:** BUTLER**Total Vertical Depth:** 2500 feet**Operator License No.:** 32693**Op Name:** HAWKINS OIL, LLC**Address:** 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2499		125 SX
SURF	8.625	216		110 SX

Well Type: OIL**UIC Docket No:****Date/Time to Plug:** 02/25/2015 8:00 AM**Plug Co. License No.:** 5870**Plug Co. Name:** PHILLIPS WELL SERVICE, INC.**Proposal Rcvd. from:** HUNT HAWKINS**Company:** HAWKINS OIL**Phone:** (918) 382-7743**Proposed Plugging Method:** AS PER KCC RULES & REGS**Plugging Proposal Received By:** JEFF KLOCK**WitnessType:** NONE**Date/Time Plugging Completed:** 02/25/2015 5:00 PM**KCC Agent:** DUANE KRUEGER**Actual Plugging Report:**

RIH ON WIRELINE SET CIBP @ 2240, DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 270'. RIH W/ TBG @ 285', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED TUBING DOWN, TOPPED WELL BACK TO SURFACE. CEMENT TICKET #48339.

Perfs:

Top	Bot	Thru	Comments
2441	2448	CSG	

Remarks: COMPLIANCE / 10 YR RULE, DENIED TA**Plugged through:** TBG**District:** 02**Signed**DUANE KRUEGER**(TECHNICIAN)****KCC WICHITA****MAY 08 2015****RECEIVED**

Form CP-2/3

5/13/15 ckm

/x