

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23743-00-00
Spot: SWNENE Sec/Twnshp/Rge: 6-26S-5E
990 feet from N Section Line, 990 feet from E Section Line
Lease Name: MARSH A Well #: 14
County: BUTLER Total Vertical Depth: 2525 feet

Operator License No.: 32693
Op Name: HAWKINS OIL, LLC
Address: 427 S BOSTON AVE STE 915
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2517		150 SX
SURF	8.625	210		110 SX
T1	2.375	2425		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2015 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: HUNT HAWKINS Company: HAWKINS OIL Phone: (918) 382-7743

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 02/25/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2425, DUMP BAILED 4 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 283.5. RIH W/TBG @ 285, CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 85 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED TUBING DOWN, TOPPED WELL BACK TO SURFACE. CEMENT TICKET #48338.

Perfs:

Top	Bot	Thru	Comments
2490	2493	CSG	
2450	2458	CSG	

Remarks: COMPLIANCE/ 10 YR RULE, DENIED TA

Plugged through: TBG

5/13/15 CKM

District: 02

Signed Duane Krueger
(TECHNICIAN)

KCC WICHITA

MAY 08 2015

RECEIVED

✓