

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25554-00-00  
Spot: S2NWSESW Sec/Twnshp/Rge: 19-16S-13W  
800 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: SALVINO Well #: 1-19  
County: BARTON Total Vertical Depth: 3520 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3520	1900	180 SX
SURF	8.625	474		350 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2015 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed  
Plugging  
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/23/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing at 1900'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 650' and pumped 50 sx cement w/100 # hulls. Pulled casing to 350'. Circulated cement to surface with 120 sx cement. Pulled casing and hole stayed full.

GPS: 38.64004 -098.80632

Perfs:

Top	Bot	Thru	Comments
3413	3417		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

5/13/15 *CM*

District: 04

Signed Bruce Rodie

(TECHNICIAN)

KCC WICHITA

CM

MAY 01 2015

MAY 11 2015

RECEIVED

Form CP-2/3