

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23649-00-00
Spot: SWNWSESW Sec/Twnshp/Rge: 14-21S-12W
903 feet from S Section Line, 1601 feet from W Section Line
Lease Name: ROBERTS Well #: 1-14
County: STAFFORD Total Vertical Depth: 3700 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3699	1713	WITH 180 SX CMT
SURF	8.625	341		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2015 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3510' WITH 5 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 380' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2015 1:35 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SANDED BACK TO 3480' WITH 5 SX CMT. 1ST PLUG AT 722' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 392' WITH 50 SX CMT. 3RD PLUG AT 37' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3589	3593		
3562	3566		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

5/13/15 CRM

District: 01

Signed Robert Dickerson

RECEIVED
MAY - 6 2015
KCC DODGE CITY



57A (TECHNICIAN)
KCC WICHITA
MAY 08 2015
RECEIVED