

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22770-00-00
Spot: SWSNWSW Sec/Twnshp/Rge: 13-32S-5E
1339 feet from S Section Line, 4359 feet from E Section Line
Lease Name: SCHOLFIELD Well #: 2
County: COWLEY Total Vertical Depth: 3149 feet

Operator License No.: 3801
Op Name: LEAKE, HENRY A. DBA GEO-SAX PETR
Address: 6882 322ND RD
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3149	1374	75 SX
SURF	8.75	304		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2015 8:00 AM
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 2939' W/ 4 SXS, PULL PIPE & CIRC. 355'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL BACK @ 2940', DUMP,BAILED 4 SXS CEMENT ON TOP. TAGGED CEMENT PLUG @ 2805'. RIH CUT CASING @ 1374', LAYED DOWN 32 JOINTS 4 1/2" CASING (1374'). RIH W/ TBG @ 360', COOPER SERVICE ESTABLISHED CIRCULATION & PUMPED 4.25 YDS 60/40 POZMIX 4% GEL (90 SXS). CEMENT DID NOT CIRCULATE. SDON. DANIELS READY MIX CEMENT TICKET #32483. 4-2-2015. TAGGED CEMENT @ 213'. 4-7-2015, RIH W/ TBG @ 210', COOPER SERVICE ESTABLISHED CIRCULATION & PUMPED 60 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. DANIELS READY MIX TICKET #032510.

Perfs:

Top	Bot	Thru	Comments
3073	3088	CSG	
2989	2996	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

5/13/15CKM

KCC WICHITA
MAY 11 2015
RECEIVED