

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20847-00-00

Spot: NW

Sec/Twnshp/Rge: 25-17S-41W

1320 feet from N Section Line, 1320 feet from W Section Line

Lease Name: NOLAN

Well #: 1-25

County: GREELEY

Total Vertical Depth: 3083 feet

Operator License No.: 33989

Op Name: BENGALIA LAND AND CATTLE COMP

Address: PO BOX 521008
TULSA, OK 74152

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2670		WITH 2 SX CMT
PROD	4.5	3083	0	WITH 635 SX CMT
SURF	8.625	281		WITH 175 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 04/13/2015 9:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DAVID HULLUM

Company: BENGALIA LAND & CATTLE

Phone: (918) 587-8022

Proposed
Plugging
Method:

PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/15/2015 10:30 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2670' WITH 2 SX CMT. 4/13/15: PEAK WIRELINE SWABBED FLUID OUT OF WELL FROM 1650' TO 1800'. WAIT ON CMT EQUIPMENT. 4/15/15: FILLED THE 4 1/2" CASING WITH CMT FROM 1800' TO 0' USING 140 SX CMT. (BLED AIR OFF CASING 3 TIMES WHILE FILLING). PRESSURE TO 200#. HOLDING. PUMP 60 SX CMT DOWN THE ANNULUS & PRESSURE TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
3012	3014		
3002	3006		
2993	2995		


Received
KANSAS CORPORATION COMMISSION
MAY 04 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

5/6/15 CKM

RECEIVED
APR 27 2015
KCC DODGE CITY