

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21516-00-00
Spot: E2SESWNE Sec/Twnshp/Rge: 29-31S-34W
3008 feet from S Section Line, 1540 feet from E Section Line
Lease Name: LAHEY TRUST C Well #: 1-29
County: SEWARD Total Vertical Depth: 5758 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4570		WITH 2 SX CMT
DVT		3251		TOC @ 1900'
PROD	5.5	5755	1471	WITH 475 SX CMT
SURF	8.625	1461		WITH 430 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/24/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: SET CIBP BELOW 4218' WITH 2 SX CMT. PLUG AT 1650' WITH 60 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2015 12:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CASING LEAK BELOW 4500', TBG STUCK AT 4500'. CUT TBG AT 4602'. SET CIBP @ 4570' WITH 2 SX CMT. 1ST PLUG AT 1623' WITH 150# HULLS & 60 SX CMT. 2ND PLUG AT 542' WITH 50 SX CMT. 3RD PLUG PUMPED 25 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4881	5314		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.


Plugged through: TBG

KCC WICHITA
APR 30 2015
RECEIVED

5/6/15CKM

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR 27 2015
KCC DODGE CITY