

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-22098-00-00
Spot: SESWSW Sec/Twnshp/Rge: 17-34S-37W
584 feet from S Section Line, 4501 feet from E Section Line
Lease Name: BLAKELY TRUST LEASE Well #: 1-17
County: STEVENS Total Vertical Depth: 6770 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5990		WITH 2 SX CMT
PROD	4.5	6767	1700	WITH 300 SX CMT
SURF	8.625	1727		WITH 525 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/15/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO LLC Phone: (316) 772-8650

Proposed Plugging Method: CIBP @ 6240' WITH 2 SX CMT. PLUG AT 1770' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2015 12:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 5990 WITH 2 SX CMT. 1ST PLUG AT 1688' WITH 150# HULLS & 50 SX CMT. 2ND PLUG AT 620' WITH 50 SX CMT. 3RD PLUG 60' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6293	6301		


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

5/6/15 CKM

District: 01

Signed



(TECHNICIAN)

RECEIVED
APR 20 2015
KCC DODGE CITY



KCC WICHITA
APR 27 2015
RECEIVED



Form CP-2/3