

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-137-20697-00-00
Spot: NENWSWNW Sec/Twnshp/Rge: 4-5S-21W
1630 feet from N Section Line, 530 feet from W Section Line
Lease Name: GLENNEMEIER Well #: 1
County: NORTON Total Vertical Depth: 3532 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 4.5 | 3513 | 2487 | 180 SX |
| SURF | | 216 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2015 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL Phone: (785) 625-5891

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls. CIBP at 3450'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2015 6:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 4 1/2" casing and pumped 50 sx cement w/200 # hulls. L-K Wireline ran in hole, shot casing off at 2487', pulled 100' of 4 1/2" casing to 2380' and pumped 100 sx cement w/200 # hulls. Pulled casing to 1624' and pumped 45 sx cement w/50 # hulls. Pulled casing to 952' and pumped 50 sx cement w/50 # hulls. Pulled casing to 196' and pumped 25 sx cement to circulate cement to surface. Pulled casing to surface. Topped off 8 5/8" surface pipe w/20 sx cement.

GPS: 39.64956N -099.70097W

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3469 | 3471 | | |
| 3368 | 3370 | | |
| 3345 | 3347 | | |

Remarks: ALLIED CEMENTING TICKET # 055708

Plugged through: CSG

5/6/15 ckm

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 16 2015

MAY 01 2015

CONSERVATION DIVISION
WICHITA, KS