

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-05213-00-00
Spot: SWNE Sec/Twnshp/Rge: 20-1S-32W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease Name: WILHELM UNIT Well #: 6
County: RAWLINS Total Vertical Depth: 4209 feet

Operator License No.: 34530
Op Name: BOW CREEK OIL COMPANY, GENERA
Address: 1304 EISENHOWER RD.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.875	4178		
PROD	5.5	4209		250 SX
SURF	8.625	369		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2015 3:00 PM
Plug Co. License No.: 33755 Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC
Proposal Rcvd. from: TONY STROUP Company: BOW CREEK OIL Phone: (785) 650-1738

Proposed Plugging Method: Ordered 140 sx 60/40 pozmix 4% gel cement w/100 # hulls.
8 5/8" surface casing set at 369' w/300 sx cement. 5 1/2" production casing set at 4209' w/250 sx cement. 2 7/8" tubing cemented in 5 1/2" casing. Cement did not circulate to surface. 2 7/8" tubing perforated at 4072' - 4084'. Perforations at 4118' - 4122' were plugged with cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2015 6:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 2 7/8" casing and pumped 95 sx cement w/100 # hulls. Pressured to 1400 psi.
Connected to 5 1/2" casing annulus and pumped 25 sx cement. Pressured to 300 psi.
Connected to 8 5/8" surface casing and pumped 20 sx cement. Pressured to 300 psi.

GPS: 39.95326N -100.93280W

Perfs:

Top	Bot	Thru	Comments
3898	4152		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1260

Plugged through: CSG

5/6/15 ckm

District: 04

Signed Darrel Dipman (TECHNICIAN) CM

APR 27 2015

Received
KANSAS CORPORATION COMMISSION Form CP-2/3
MAY 01 2015
CONSERVATION DIVISION