

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-03279-00-00
Spot: NWSEW Sec/Twnshp/Rge: 10-10S-25W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: ELRICK UNIT Well #: 11-2
County: GRAHAM Total Vertical Depth: 4023 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4021		150 SX
SURF	8.0625	201		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2015 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DENNIS Company: CITATION OIL AND GAS Phone: (281) 891-1000

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 1937' w/100 bbls Ken Pack.
Perforations: 3778' - 3784', 3792' - 3798', 3827' - 3830', 3838' - 3841', 3875' - 3878', 3885' - 3888', 3933' - 3938', 3976' - 3978', 3998' - 4001'.
Packer stuck in hole at 3697'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2015 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3662' and pumped 120 sx cement. Pulled tubing to 2940' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2068' and pumped 235 sx cement w/250 # hulls. Good circulation of cement. Pulled tubing out and topped off with 15 sx, full. Tied on to backside and squeezed with 30 sx cement. Shut in pressure 300 psi.

GPS: 39.19986 -100.10213

Perfs:

Top	Bot	Thru	Comments
3998	4001		
3976	3978		
3933	3938		
3885	3888		
3875	3878		
3838	3841		
3827	3830		
3792	3798		
3778	3784		

Remarks: ALLIED CEMENT TICKET # 55752

Plugged through: TBG

District: 04

Signed _____

(Handwritten Signature)
(TECHNICIAN)

5/6/15CKM

CM

APR 15 2015

KCC WICHITA

APR 24 2015

RECEIVED