

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-03656-00-00  
Spot: NWSENENE Sec/Twnshp/Rge: 36-8S-18W  
721 feet from N Section Line, 575 feet from E Section Line  
Lease Name: MADDY A Well #: 1  
County: ROOKS Total Vertical Depth: 3412 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3406		75 SX
SURF	8.625	135		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2015 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DENNIS MICK Company: CITATION OIL & GAS CORP. Phone: (281) 891-1000

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Used pump and power swivel to drill. Drilled for 2 days and made 11' to 2860'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/09/2015 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Perforated at 1850', 1300' and 680'. Ran tubing to 2850' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1900' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 900' and pumped 100 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Hooked to 5 1/2" casing and pumped 35 sx cement to top off 5 1/2" casing. Visually checked 8 5/8" x 5 1/2" annulus and cement was to surface.

GPS: 39.31913N -099.27178W

Remarks: ALLIED CEMENTING TICKET # 055663

Plugged through: TBG

5/6/15 CKM

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 29 2015

MAY 01 2015

CONSERVATION DIVISION  
WICHITA, KS