

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26091-00-00
Spot: SENWSWSE Sec/Twnshp/Rge: 25-16S-13W
905 feet from S Section Line, 2240 feet from E Section Line
Lease Name: STEINER Well #: 1-25
County: BARTON Total Vertical Depth: 3385 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	853		325 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/22/2015 12:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Revd. from: GAYLON Company: DUKE DRILLING CO., INC. Phone: (620) 786-1728

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE
Date/Time Plugging Completed: 04/22/2015 2:00 PM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @3361 w/50 sx
2nd plug @910 w/50 sx
3rd plug @500 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: BASIC

Plugged through: DP

District: 04

Signed Chris Neeley

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

MAY 01 2015

Form CP-2/3

APR 23 2015

CONSERVATION DIVISION
WICHITA, KS