

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-01610-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 9-9S-24W  
3676 feet from S Section Line, 1713 feet from E Section Line  
Lease Name: KEITH Well #: 5  
County: GRAHAM Total Vertical Depth: 4025 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4024		250 SX
SURF	8.625	263		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2015 10:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING-NELSON OIL CO. INC. Phone: (785) 621-2610

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.  
Production perforations: 3926' - 3961'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/25/2015 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3800' and pumped 11 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 2450' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1200' and pumped 30 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement at 200 psi.

GPS: 39.28694N -100.00169W

Perfs:

Top	Bot	Thru	Comments
3955	3961		
3926	3932		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1227

Plugged through: TBG

*5/6/15CPM*

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

APR 14 2015

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 01 2015

CONSERVATION DIVISION  
WICHITA, KS