

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22186-00-03
Spot: NWNE Sec/Twnshp/Rge: 17-30S-13W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: LAMBERT B Well #: 1-17
County: BARBER Total Vertical Depth: 4780 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	103		
PROD	4.5	4775	2400	WITH 225 SX CMT
SURF	8.625	1081		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/03/2015 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT 4500'. PLUG AT 1120' WITH 10 SX GEL & 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2015 1:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

PUMP DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX CMT. SHUT IN WITH 200 PSI. TAGGED TOC @ 4480'. 1ST PLUG AT 1136' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 623' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4550	4568		
4450	4568		
4400	4410		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL.

Plugged through: CSG

5/6/15 CKM

District: 01

Signed Robert Dickerson
(TECHNICIAN)

5A

RECEIVED
APR 16 2015
KCC DODGE CITY

MP