

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-60010-00-01
Spot: NESENE Sec/Twnshp/Rge: 29-20S-9W
3634 feet from S Section Line, 341 feet from E Section Line
Lease Name: KEESLING WALTER Well #: 1
County: RICE Total Vertical Depth: 3290 feet

Operator License No.: 33725
Op Name: FOUNDATION ENERGY MANAGEMEN
Address: 16000 NORTH DALLAS PKWY, STE 875
DALLAS, TX 75248

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3190		
PROD	4.5	3290		130 SX
SURF	8.625	209		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2015 10:00 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: CASEY HALL Company: FOUNDATION ENERGY MGMT Phone: (918) 896-9232

Proposed Plugging Method: PER KCC INSTRUCTIONS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 04/27/2015 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 3190' AND CAP WITH 4 SX'S CEMENT.
ATTEMPTED TO MIT CASING - MIT FAILED. PERFORATE AT 1225', AND 775', AND 260'. RUN TUBING TO 1225' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 775'. LET SET FOR 1.5 HOURS AND TAGGED CEMENT AT 950'. PUMPED 35 SX'S AT 775', PULLED TUBING TO 260' AND CIRCULATED CEMENT TO SURFACE - UP BOTH CASINGS. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3241	3244		
3232	3235		

Remarks: XCEL PERF TICKET #0803. COPELAND CEMENT #41239. WELL WAS DENEID TA STATUS DUE TO HFLD.

Plugged through: TBG

5/6/15 ckm

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION Form CP-2/3

MAY 05 2015

CONSERVATION DIVISION
WICHITA, KS

1/8