

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21313-00-01
Spot: NESWSW Sec/Twnshp/Rge: 2-26S-4E
976 feet from S Section Line, 4266 feet from E Section Line
Lease Name: PAULSON Well #: 6A
County: BUTLER Total Vertical Depth: 2446 feet

Operator License No.: 5446
Op Name: GILES, BENJAMIN M.
Address: 346 S. LULU
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2445	247	150 SX
SURF	8.63	150		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2015 8:30 AM
Plug Co. License No.: 5446 Plug Co. Name: GILES, BENJAMIN M.
Proposal Revd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-1288

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2015 2:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) SET CIBP ABOVE ARBUCKLE AND CAP W/2 SKS CEMENT. 2) CUT CASING AT APPROX 249' AND PULL 4.5" OUT OF HOLE. 3) TIED ONTO TUBING SET AT 255' AND PUMPED 145 SKS OF 60/40 4% CEMENT W/ 6 SKS OF HULLS. CEMENT CIRCUALTED TO SURFACE. 4) WITNESSED CEMENT AT SURFACE ON 4/9/2015. 5) CASING CUT OFF AT APPROX. 5' AND BURIED.

Perfs:

Top	Bot	Thru	Comments
2412	2424	CSG	

Remarks: CEMENTING COMPELTED BY GRESSEL OIFLEILD SERVICE, LLC. TICKET #43051. PLUGGED DUE TO COMPLIANCE W/ K.A.R. 82-3-1011.

Plugged through: TBG

5/6/15ckm

District: 02

Signed Jonathan Hill

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

APR 23 2015

CONSERVATION DIVISION
WICHITA, KS

JK