

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21425-00-00
Spot: SENWSW Sec/Twnshp/Rge: 2-26S-4E
1646 feet from S Section Line, 4257 feet from E Section Line
Lease Name: PAULSON Well #: 4A
County: BUTLER Total Vertical Depth: 2430 feet

Operator License No.: 5446
Op Name: GILES, BENJAMIN M.
Address: 346 S. LULU
WICHITA, KS 67211

String 'Size	Depth (ft)	Pulled (ft)	Comments
CIBP	2000		
PROD 4.5	2428		156 SX
SURF 8.625	150		100 SX
T1 2.875	2000		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2015 8:30 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-1288

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2015 2:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) CIBP SET AT 2000' AND CAPPED WITH CEMENT BACK TO 1950'. 2) PERFORATED AT 250'. 3) 1.25" COILED TUBING RAN INTO 260' AND PUMPED 175 SKS OF 60/40/4% CEMENT W/ NO ADDITIVES. CIRCULATED TO SURFACE INITIALLY (WELL WENT ON VACUUM WHILE CEMENTING). 4) DROPPED LINE TO TAG TOP OF CEMENT INSIDE 4.5" CASING, CEMENT FELL BACK > 300'. 5) TIED ONTO 4.5" CASING AND PUMPED 160' SKS CEMENT W/ 7 SKS HULL, CIRCULATED TO SURFACE. 6) CEMENT FELL ON BACKSIDE -- TOPPED OFF ON 4/9/15 WITH 0.25 SKS PER DUSTY GREEN. 7) WITNESSED CEMENT AT SURFACE ON 4/9/2015. 8) CASING CUT OFF APPROX. 5' DOWN AND BURIED.

Perfs:

Top	Bot	Thru	Comments
2394	2396	CSG	
1956	1958	CSG	

Remarks: CEMENTING COMPLETED BY GRESSEL OILFIELD SERVICE, LLC. TICKET #43049. PLUGGED DUE TO COMPLIANCE W/ K.A.R. 82-3-1011.

Plugged through: TBG

5/6/15 CKM

District: 02

Received Jonathan Hill
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

APR 23 2015

CONSERVATION DIVISION
WICHITA, KS

JK

Form CP-2/3