

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-21484-00-00  
Spot: NWNWNWSW Sec/Twnshp/Rge: 2-26S-4E  
2317 feet from S Section Line, 4959 feet from E Section Line  
Lease Name: PAULSON Well #: 5B  
County: BUTLER Total Vertical Depth: 2433 feet

Operator License No.: 5446  
Op Name: GILES, BENJAMIN M.  
Address: 346 S. LULU  
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2001		
PROD	4.5	2432		200 SX
SURF	8.625	150		85 SX
T1	2.875	1800		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2015 8:30 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Revd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-1288

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/08/2015 2:00 PM KCC Agent: JONATHAN HILL

**Actual Plugging Report:**

1) RAN IN HOLE AND TAGGED CIBP AT 700', SET A NEW CIBP AT 580' AND CAPPED W/ 2 SKS CEMENT. 2) PERFORATED AT 250'. 3) 1.25" COILED TUBING RAN IN TO 260' AND PUMPED 45 SKS OF 60/40 4% CEMENT W/NO ADDITIVES. CIRCUALTED TO SURFACE. 4) WITNESSED CEMENTED AT SURFACE ON 4/9/2015. 5) CASING CUT OFF APPROX. 5' DOWN AND BURIED.

**Perfs:**

Top	Bot	Thru	Comments
2366	2433	CSG	
1953	1966	CSG	
626	640	CSG	

Remarks: CEMENTING COMPELTED BY GRESSEL OILFIELD SERVICE, LLC. TICKET #43050. PLUGGED DUE TO COMPLIANCE W/ K.A.R. 82-3-1011.

Plugged through: TBG

5/6/15 CKM

District: 02

Signed Jonathan Hill  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

APR 23 2015

CONSERVATION DIVISION  
WICHITA, KS