

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26084-00-00
Spot: W2SEW Sec/Twnshp/Rge: 14-16S-12W
1980 feet from N Section Line, 1650 feet from W Section Line
Lease Name: HOFFMAN Well #: 1
County: BARTON Total Vertical Depth: 3421 feet

Operator License No.: 33921
Op Name: GRA EX, LLC
Address: 2435 N MARQUETTE PO BOX 32
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	414		200 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/11/2015 12:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: STEVE Company: ROYAL DRILLING INC Phone: (785) 735-4142

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE
Date/Time Plugging Completed: 03/11/2015 2:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

1st plug @3400 w/50 sx
2nd plug @810 w/50 sx
3rd plug @470 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

5/6/15 ckm

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CM

APR 15 2015

MAY 01 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS