

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-21286-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 13-15S-19W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease Name: WOLFE Well #: 1  
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 33625  
Op Name: HERTEL OIL COMPANY LLC  
Address: 704 E 12TH ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3685		125 SX
SURF	8.625	1223		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/21/2015 2:00 PM  
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC  
Proposal Rcvd. from: MIKE HERTEL Company: HERTEL OIL CO. LLC Phone: (785) 628-2445

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 200 sx common.  
Alt II completion  
Perforations- LKC 3505' - 3508', 3483' - 3487'.  
Casing is in good shape. Low Fluid level.  
Cementers did not bring gel or hulls as ordered.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2015 4:00 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

**Perfs:**

Rigged to 5 1/2" casing with a swedge and pumped 400 sx 60/40 pozmix cement to pressure with 200 psi. Shut in pressure 100 psi. Rigged to 8 5/8" casing with instant pressure at 250 psi. Shut in pressure 200 psi.


GPS: 38.74856N -099.37857W  
2966' FSL 1001' FEL  
NW SW SE NE

Remarks: BASIC CEMENTING CO TICKET # 1718-12414-A

Plugged through: CSG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

CM

5/6/15 CKM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAY 01 2015

CONSERVATION DIVISION  
WICHITA, KS

APR 23 2015