

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-24001-00-00
Spot: NESWNE SW Sec/Twnshp/Rge: 21-15S-15W
1760 feet from S Section Line, 1820 feet from W Section Line
Lease Name: STEINERT B Well #: 3
County: RUSSELL Total Vertical Depth: 3440 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3440	1480	180 SX
SURF	8.625	925		375 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2015 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVE FUNK Company: JASON OIL COMPANY Phone: (785)483-4204

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2015 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/16/2015--Sanded bottom off and spotted 5 sx cement on top.
04/17/2015- Tried to cut casing at 2260' and 2175'. Could not pull casing free.
04/20/2015- Shot casing at 1480'. Pulled casing to 1440' and pumped 125 sx cement w/300 # hulls. Pulled casing to 925' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450' and pumped 75 sx cement. Circulated cement into the cellar. POOH. Cellar stayed full of cement. Pulled 35 joints of 5 1/2" casing equal to 1480'. Left 1960' of casing in well.
GPS: 38.73046 -098.99785

Perfs:

Top	Bot	Thru	Comments
3306	3312		
3282	3286		
3196	3200		
3124	3128		
3104	3108		
3068	3073		

Remarks: QUALITY CEMENTING TICKET # 1806

Plugged through: CSG

5/6/15 ckm

District: 04

Signed Ray Dinkel

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

APR 27 2015

MAY 01 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS