

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25661-00-00  
Spot: NWSENE SW Sec/Twnshp/Rge: 19-16S-13W  
1910 feet from S Section Line, 2010 feet from W Section Line  
Lease Name: SALVINO Well #: 3-19  
County: BARTON Total Vertical Depth: 3479 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3479	2225	205 SX
SURF	8.625	900		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2015 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KASSLMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/21/2015 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded the bottom back to 3330' w/5 sx cement on top. Cut pipe. Pulled casing to 1470' and pumped 125 sx cement w/200 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 650' and pumped 50 sx cement w/100 # hulls. Pulled casing to 350' and pumped 75 sx cement. Circulated cement to pit. POOH. Cellar stayed full of cement. Pulled 52 joints of 5 1/2" casing and 20' landing joint equaling 2225'. Left 1254' of casing in well.

GPS: 38.64310 -098.80508

Perfs:

Top	Bot	Thru	Comments
3382	3386		

Remarks: COPELAND ACID & CEMENTING TICKET # 41218

Plugged through: CSG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 27 2015

MAY 01 2015

CONSERVATION DIVISION  
WICHITA, KS