

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1967
2-27-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued December 13, 1966.

Operator's Full Name Union Oil Company of California

Complete Address: 2000 Classen Center, Oklahoma City, Oklahoma

Lease Name Sankey Coberly Well No. # 1

Location C NW SW Sec. 2 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4246'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:00 P M Day 22nd Month Feb. Year 1967

The Above well was plugged as follows:

268' of 8 5/8" surface pipe, cemented with 225 sacks. 4245' of 5 1/2" long
string, cemented with 125 sacks. Plug back T.D. 4181'. Top perferation
3804'. All perferation were squeezed with 100 sacks of cement, bringing
the top of the cement to 3650' in the 5 1/2". 2706' of 5 1/2" long string was
recovered from the hole. Hole was filled with mud to 250', rock bridge
from 250' to 240', and cemented with 25 sacks. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 2/27/67

INV. NO. 4831-W