

R

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

SEP 12 1966

9-12-66

CONSERVATION DIVISION
Wichita, Kansas

Sept. 9, 1966.

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg. Wichita, Kansas.

Lease Name Wilson Well No. #2

Location C-NW-SE-SW Sec. 2 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4255'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 342 Eldorado, Kansas. License No. 547

Operation Completed: Hour 2:30 PM Day 9 Month Sept Year 1966

The Above well was plugged as follows:

210' of 8 5/8" surface pipe circulated with 165 sacks cement. Top
perforation at 4162'. Hole sanded to 4150' & 5 sacks cement, with baler.
Hole filled with mud to 200'. 10' rock bridge & 25 sacks cement. Hole
filled with mud to 40', 10' rock bridge & 10 sacks cement to base of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Herman Gustus
Well Plugging Supervisor

DATE: 9-12-66

INV. NO. 3907-W