

KANSAS

M
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl Bldg Wichita, Ks

Lease Name Maple C Well No. 1

Location NW/SW/NE Sec. 1 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4181

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1182 Great Bend, Ks License No. 623

Operation Completed: Hour 10:00 AM Day 3 Month 10 Year 1972

The above well was plugged as follows:

242 ft 8 5/8 surface pipe cemented with 165 sacks. 4180 ft 5 1/2 long
string cemented with 90 sacks. Top perf. 4092 ft. Sand to 4050 ft,
5 sacks cement with bailer. Pulled 3340 ft 5 1/2. Set 10 ft rock bridge
at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed *L. Russell B. Bunting*
Well Plugging Supervisor

DATE 10/4/72
INV. NO. 6423-W