

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name Reida Well No. # 3

Location NW SW SW Sec. 1 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4192

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 4:00PM Day 8th Month May Year 1963

The Above well was plugged as follows:

254' of 8 5/8" surface pipe, cement circulated with 170 sacks. 4189' of
5 1/2" long string, cemented with 100 sacks. Plugged back to 4152'. Perfor-
ated 4102'. Sanded to 4090', cemented with 5 sacks. Hole was filled with
mud to 225', 10' rock bridge, cemented with 20 sacks. Hole filled with
mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.
3525' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/13/63

INV. NO. 4069-W

Signed: Archie Elving
Well Plugging Supervisor