

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed August 10, 1967.

Operator's Full Name Theodore R. Ferguson

Complete Address: 1525 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name Harold L. Reida Well No. # 1

Location C SE NE Sec. 32 Twp. 30 Rge. 6 (E) (W)

County Kingman Total Depth 4730'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: E. K. Edmiston Drilling Company, Inc.

Address: 425 First National Bank Bldg., Wichita, Ks. License No. _____

Operation Completed: Hour 10:30AM Day 30th Month August Year 1967

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated with 180 sacks. Hole was filled with drilling mud to 240', 1st cementing plug, bridged with 1/2 sack of hulls on fluid at 240', and cemented with 25 sacks, with cement from 230' to 155'. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks, with cement from 30' to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 9/6/67
INV. NO. 6263-W