

*RP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Drillers Production Company, Inc.  
 Complete Address: 480 Fourth National Bank Bldg., Wichita, Kansas  
 Lease Name Lock "B" Well No. # 1  
 Location C NW NW Sec. 13 Twp. 30 Rge. 7 (E) (W) W  
 County Kingman Total Depth 4133'  
 Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
 Other well as hereafter indicated:       
 Plugging Contractor: Knight Casing Pulling Company  
 Address: Box 405, Chase, Kansas License No. 436  
 Operation Completed: Hour 1:00AM Day 13th Month Oct. Year 1966

The Above well was plugged as follows:

268' of 8 5/8" surface pipe, cemented with 125 sacks. 4124' of 5 1/2" long  
string, cemented with 100 sacks. Plug back T.D. 3739'. Top perferation  
3717'. Bottom of the hole was sanded to 3700', and cemented with 5 sacks,  
through the dump bailer. 3475' of 5 1/2" long string was recovered from the  
hole. Hole was filled with mud to 265', rock bridge from 265' to 255',  
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge  
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 10/19/66  
INV. NO. 4114-u