

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 1 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill,
filed December 14., 1967.

Operator's Full Name Clinton Oil Company

Complete Address: 6810 W. Highway 54, Wichita, Kansas

Lease Name Legg Well No. # 1-V

Location C SE SW Sec. 9 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4225'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas 67530 License No.

Operation Completed: Hour 7:00PM Day 8th Month January Year 1968

The Above well was plugged as follows:

251' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole was
filled with drilling mud to 240', 1st cementing plug, bridged with 1 sack
of dry cement and 1/2 sack of hulls on fluid at 240', and cemented with 24
sacks, with cement from 230' to 155'. Hole was filled with drilling mud to
40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack of
hulls on fluid at 40', and cemented with 9 sacks, with cement from 30' to
the base of the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/21/68
INV. NO. 7070-W

Signed: Archie Elving
Well Plugging Supervisor