

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
SEP 15 1966  
9-15-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Sept 8, 1966.

Dear Sir:

Mr. Kenneth Smith of Elint Engineering & Const. has this date requested permission to plug the following described well:

Mr. Kenneth Smith guarantees payment of the plugging fee.

Operator's full Name: H. C. Bennett

Complete Address: 1212 Union National Bldg. Wichita, Kansas.

Lease Name: Krehbiel A #2 Well No. A #2

Location: NW-SW-NE Sec. 2 Twp. 30 Rge. 7 (E)(W) W

County Kingman Total Depth 4212' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Kenneth Smith was instructed to plug the well as follows:

4177' of 5 1/2" long string, Open hole. Sand to 4170' & 5  
sacks cement. 211' of 8 5/8" surface pipe circulated with  
100 sacks of cement. Mud to 200', 10' rock bridge & 25 sacks  
cement. Mud to 40', 10' rock bridge, 10 sacks cement to base  
of cellar.

Very truly yours,

Herman Justus  
Conservation Division Agent