

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1966

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Sept. 8, 1966.

Dear Sir:

Mr. Kenneth Smith of Flint Engineering & Construction Co.

date requested permission to plug the following described well:

Mr. Kenneth Smith guarantees payment of the plugging fee.

Operator's full Name: H. C. Bennett

Complete Address: 1212 Union National Building Wichita, Kansas.

Lease Name: Wilson Well No. #2

Location: C-NW-SE-SW Sec. 2 Twp. 30 Rge. 7 (E)(W) X

County Kingman Total Depth 4255' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole
Abandoned

Mr. Smith was instructed to plug the well as follows:

210' of 8 5/8" surface pipe circulated with 165 sacks
cement. Top perforation 4162'. Hole sanded to 4150' & 5 sacks
cement per baler. Hole filled with mud to 200'. 10' rock bridge
and 25 sacks cement. Hole filled with mud to 40', 10' rock
bridge & 10 sacks cement into base of cellar.

Very truly yours,

Herman J. Gustus
Conservation Division Agent