

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 13 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling has this

date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kans.

Lease Name: Reida Well No. # 3

Location: NW SW SW Sec. 1 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4192 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

254' of 8 5/8" surface pipe, cement circulated with 170

sacks. 4189' of 5 1/2" long string, cemented with 100 sacks.

Plugged back to 4152'. Perferated 4102'. Sand to 4090'.

cement with 5 sacks. Fill hole with mud to 225', 10' rock

bridge, cement with 20 sacks. Fill hole with mud to 40',

10' rock bridge, cement with 10 sacks to base cellar.

Very truly yours,

Audie Elving
 Conservation Division Agent