

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Berens of D.N.B. Drlg Inc has this

date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.

Operator's full Name: National Oil Co.

Complete Address: Garvey Bldg Wichita, KS

Lease Name: Van Geison Well No. 1

Location: G SW/NE Sec. 33 Twp. 30s Rge. 6 (E)(W) W

County: Kingman Total Depth 4672 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Berens was instructed to plug the well as follows:

200 ft 8 5/8 surface cemented with 150 sacks. Fill hole

to 175 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud to

40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

[Signature]  
Conservation Division Agent