

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 25 1962  
 11-2-62  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Albert Schisner of Forbes Caseing Pulling Co. has this Oct. 25, 62 date requested permission to plug the following described well:

Mr. Albert Schisner guarantees payment of the plugging fee.

Operator's full Name: Forbes Caseing Pulling Co.

Complete Address: Box 221 Great Bend Kansas.

Lease Name: T. J. Thompson Well No. #1

Location: NW SW SW Sec. 11 Twp. 30 Rge. 7 (E) (W) X

County Kingman Total Depth 4116' Oil Well

Abandoned  
 Gas Well X Input Well  SWD Well  D & A  Lost Hole

Mr. Albert Schisner was instructed to plug the well as follows:

4116' of 5 1/2" oil string. Top perforation at 4108'. Squeezed  
to 3300' with 20 sacks cement by Globe Cementing Co. Hole  
filled to 150' with mud, 10' rock bridge and 20 sacks cement.  
Hole filled to 40' with mud, 10' rock bridge and 10 sacks  
cement to base of cellar.

Very truly yours,

Herman Gustas  
 Conservation Division Agent