

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 26 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling has this date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Ks.

Lease Name: Muller Well No. # 1

Location: SW SW NW Sec. 11 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4200 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Deacon was instructed to plug the well as follows:

201' of 8 5/8" surface pipe cemented with 160 sacks.
4198' fo 5 1/2" long string cemented with 90 sacks. Plugged
back to 4152'. Perferated at 4139'. Sand to 4125'. cement
with 5 sacks. Fill hole to 210', 10' rock bridge, cement
with 20 sacks. Fill hole with mud to 40', 10' rock bridge,
cement with 10 sacks to base cellar.

Very truly yours,

Archie Cliving
 Conservation Division Agent