

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
Filed December 14, 1967.

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 6810 W. Highway 54, Wichita, Kansas

Lease Name: Legg Well No. # 1-V

Location: C SE SW Sec. 9 Twp. 30 Rge. 7 (E)(W) W

County Kingman Total Depth 4225' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

251' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sacks

Very truly yours,

Aubrie Elving
Conservation Division Agent