

State of Kansas

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 4 1963  
 11-4-63

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Percy Hall of Pickrell Drilling Co. has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Ks.

Lease Name: Early "A" Well No. # 2

Location: NE SE SW Sec. 3 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4225 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

201' of 8 5/8" surface pipe, cemented with 150 sacks.

Fill hole with drilling mud to 225', 1st cementing plug,

1/2 sacks hulls, cement with 25 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement

with 10 sacks to base cellar. Bridge and cement rat hole

with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent