

1031550

15-025-20300-00-00

TO: STATE CORPORATION COMMISSION

API NUMBER _____ NW SE NW SEC. 29 T 31 S, R 21 W

CONSERVATION DIVISION - PLUGGING SECTION 1700 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1400 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MOORE WELL # 4-29

TECHNICIAN'S PLUGGING REPORT

5/19

COUNTY CLARK 173.88

OPERATOR LICENSE # 4058

WELL TOTAL DEPTH 5350 FEET

OPERATOR: AMERICAN WARRIOR

PRODUCTION CSG: SIZE 5 1/2" @ 5356' WITH 250 SX

NAME AND PO BOX 399

SURFACE CASING: SIZE 8 5/8" @ 630' WITH 400 SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL GAS WELL INPUT WELL ~~203779~~ SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187 MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 9:45 AM DAY: 19 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 5161-5180

MIX AND PUMP 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG AND 150 SX CEMENT. MAXIMUM PRESSURE AT 490#. SHUT IN WITH 400#.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:35 AM DAY: 19 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

MIX AND PUMP 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG AND 150 SX CEMENT. MAXIMUM PRESSURE 490#. SHUT IN PRESSURE 400#.

RECEIVED STATE CORPORATION COMMISSION

MAY 24 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFTS. RECOVERED 2740' OF 5 1/2" CASING.

CONSERVATION DIVISION Wichita, Kansas

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE

5/25/00

SIGNED

Steve Durrant

WV. NO.

61771

(TECHNICIAN)

FORM CP-2/3

(Signature)