

1 050201

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,789-0000
NE/4 SW/4
NE/4, SEC. 32, T. 31 S, R. 21 ~~W/4~~

1650 feet from ~~N/4~~ section line
1650 feet from ~~W/E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5236

Lease Name Haerberle Well # 1-32

Operator: Plains Resources, Inc.

County Clark

Name & Address 2200 Classen Blvd., Suite 2000

Well Total Depth 5400 175.50 feet

Oklahoma City, OK 73106

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 770

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Company License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 9:00 pm Day: 22 Month: April Year: 19 84

Plugging proposal received from Harvey Moore, Jr.

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2230' with 50 sx cement 2nd plug at 1100' with 50 sx cement

3rd plug at 820' with 40 sx cement 4th plug at 400' with 40 sx cement

solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rathole with 15 sx cement

8th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 pm Day: 22 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2230' with 50 sx cement, 2nd plug at 1100' with 50

sx cement, 3rd plug at 820' with 40 sx cement, 4th plug at 400' with 40 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rathole with 15 sx cement, 8th plug to circulate mousehole with

10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form)

(If disk is used) observe this plugging.

INVOICED

DATE 5-7-84

INV. NO. 1391

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

MAY 03 1984

CONSERVATION DIVISION Wichita, Kansas