

To: 1 040098  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA; KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5205

Operator: Mid-Continent Energy Corporation  
Name & Address 155 North Market, Suite 200  
Wichita, KS 67202-1816

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:45 a.m. Day: 10 Month: 5 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4486' Perfs at 4452-56'

1st plug pump 4 sx hulls and 60 sx cement to bottom,

2nd plug shoot at 680' to 700', squeeze with 150 sx 65-35.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 9:30 a.m. Day: 10 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 30 sx cement. Well went on vacuum.  
Went 10' below perfs, pumped 5 sx hulls and 30 sx cement, squeezed off at 3540'.

2nd plug pumped down 4 1/2" with 100 sx cement. Maximum pressure 600 psi and shut in 400 psi.  
Backside never blew or circulated.

Then we pumped down 8 5/8" and 4 1/2" annulus with 3/4 barrel of water and it pressure up  
to 750 lbs. Would not bleed off. Bled back to 200 lbs. and shut in. RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. No casing recovery. 5-13-88  
(If additional description is necessary, use BACK of this form.) MAY 13 1988

INVOICED (if applicable) observe this plugging.

DATE 5-17-88

INV. NO. 20642

Signed Stephen J. Pfeiffer  
(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas