

To: 1040904 11-7
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-NA-15-007-00436-00-01
NW SE NW, SEC. 25, T 7 S, R 13 W.
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3532
Operator: CMX, Inc.
Name & Address 150 N. Main, Ste. 1026
Wichita, KS 67202

Lease Name Roessler OWWO Well # 1-B
County Barber
Well Total Depth 4320 140.40 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 217

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Hardtner Well Service License Number 30607
Address 150 N. Main, Ste. 1026, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 7 Month: 11 Year: 19 94

Plugging proposal received from Mority Baessler
(company name) Hardtner Well Service (phone) 316-269-9052

vers: 5 1/2" at 4315' w/200 sx cement, Perfs at 4220-40'
1st plug sand back to 4170' and dump 5 sx cement on top of sand through bailer.
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:45 a.m. Day: 7 Month: 11 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4170' and dumped 5 sx cement on top of
sand bridge through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 150 sx cement.
Maximum pressure 750 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1980' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.) NOV 7 1994

INVOICED observe this plugging.

DATE 12-2-94
INV. NO. 41780

Signed Stephen J. [Signature]
(TECHNICIAN)
STATE CORPORATION COMMISSION
WICHITA, KANSAS
FORM C
Rev.