

1 040345

11-2

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,915-00-00
C SW SW, SEC. 25, T 31 S, R 13 W/E
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5303

Lease Name Catlin Well # 1

Operator: Canaday Oil Corporation
Name & Address 920 North Tyler, Suite 104
Wichita, KS 67212

County Barber 147.06

Well Total Depth 4525 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 2 Month: 11 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 3790' PBD 3790' Perfs at 3620-24'

1st plug sand back to 3570' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 2 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3570' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 850 psi and shut in 700 psi.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 7 1989

11-7-89

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% cc 3% gel by Allied. Recovered 2500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(do not observe this plugging.)

DATE 11-13-89

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 26283

11-2