

To: 1040926 12-30  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,760-0000  
NE NE NE, SEC. 28, T 31 S, R 13 W/E  
4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Operator: CMX, Inc.  
Name & Address 150 N. Main, Ste. 1026  
Wichita, KS 67202

Lease Name Paul Thomas Well # 1

County Barber

Well Total Depth 4637 150.70 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hardtner Well Service License Number 30607

Address 150 N. Main, Ste. 1026, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 30 Month: 12 Year: 19 94

Plugging proposal received from Sam Flying Out

(company name) CMX, Inc. (phone) 316-269-9052

Work: 5 1/2" at 4636' w/260 sx cement, Perfs at 4256-61'

1st plug set CIBP at 4200' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:45 a.m. Day: 30 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4160' and dump 2 sx cement on top through  
bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 1000 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2501' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

DATE 1-9-95

INV. NO. 42011  
12-30

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 05 1995  
CONSERVATION DIVISION  
WICHITA, KANSAS