

8-16

1 040454

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19-007-21,877-6000  
SE NE, SEC. 28, T 31 S, R 13 W/E  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3532

Lessee Name Mel Alson Well # 1

Operator: CMX Inc.  
Name & Address 1026 Union Center Bldg.  
Wichita, KS 67202

County Barber 137.54

Well Total Depth 4232 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:15 p.m. Day: 16 Month: 8 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4232' w/260 sx cement, PBD 4200', Perfs at 3359-64' Elevation 1576' GL  
1st plug sand back to 50' above the perforations with 5 sx cement on top,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,  
release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 16 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3309' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6 1/2" set by services. Recovered 2350' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED

AUG 24 1990 8-24-90

INVOICED

DATE 8-29-90

INV. NO. 29145

CONSERVATION DIVISION  
Wichita, Kansas

Signed Stephen J. Pfeiffer  
(TECHNICIAN)